# **Update on the Lone Cabbage Reef Restoration Project in Suwannee Sound**


Peter Frederick, Bill Pine, Leslie Sturmer, <u>Steve Beck</u> University of Florida

Oyster Integrated Mapping and Monitoring Program Workshop
22-23 May 2018






### PROJECT AREA:



Raabe, E. A., A. E. Streck, R. S. Stumpf. 2004. Historic topographic sheets to satellite imagery: A methodology for evaluating coastal change in Florida's Big Bend tidal marsh. USGS Open File Report 02-211

## Degradation of Lone Cabbage Reef



### Intertidal Oyster Reef Change in the Big Bend Region

#### Reef Loss 1982-2011

• Offshore: 88%

• Nearshore: 61%

• Inshore: 50%

• Lone Cabbage Area: 70%




Seavey, J. R., W. E. Pine, III, P. Frederick, L. Sturmer, and M. Berrigan. 2011. Decadal changes in oyster reefs in the Big Bend of Florida's Gulf Coast. Ecosphere 2(10):114. doi:10.1890/ES11-00205.1

### Possible Causes of Oyster Reef Change


Are changes in Suwannee River discharge patterns affecting oyster populations?







# Possible Causes of Oyster Reef Change

### Is overfishing negatively affecting reefs?








# Oyster reefs as barriers

### • GOALS:

- Ecosystem response to barrier reef restoration
  - Restore/Maintain estuarine conditions
  - Coastal protection
  - Habitat, WQ improvement
- Local Oyster Restoration
  - Provide durable substrate
- Model for other similarly degraded reefs in Big Bend Region





# Adding Substrate Works

- Builds on Pilot Project success
  - 9.2x increase in oyster density




Frederick, P., N. Vitale, B. Pine, J. Seavey, L. Sturmer. 2016. Reversing a rapid decline in oyster reefs: effects of durable substrate on oyster populations, elevations, and aquatic bird community composition. Journal of Shellfish Research. 35(2):359-367.



# Lone Cabbage Reef Restoration Project

- Restore to mid 1800's extent
- 22 reef elements
- 7.26 acres
  - ~3 linear miles (5 km)
  - 30 ft wide
- 16,894 cu yrds of rock
- 8-10" local limerock
- Topped with clam/oyster shell
- 85% of project funding = construction



### **Restoration Predictions**

- 1. Rapid repopulation of oysters and reef fauna following episodic dieoffs
- 2. Increased resilience of oyster populations to low flow events
- 3. Decreased salinities in Suwannee Sound and landward marshes
- 4. Shifts in community composition: food web alterations



Pilot Project -> 18 months post construction



# Monitoring Efforts: Water Quality

· Will reef construction affect hydrologic regime?

#### Continuous recorders:


- Nine sensors deployed August 2017
- Hourly: Salinity, Temperature, Depth

### Water Chemistry (UF funded):

• Monthly: chlorophyll, N, P, color, turbidity

#### In Progress:

- Compilation of Cooperator WQ Data
  - FWC, FDACS, Dr. Tom Frazer
- Exploring river discharge/salinity relationships (USGS)



# Monitoring Efforts: Oysters

- Will reef construction affect oysters?
- Intertidal Reef Metrics:
  - Live/Dead oyster density (Annual)
  - Oyster height distribution (Annual)
  - Recruitment (Monthly)
- Continue/Expand Pilot Project Methods:
  - Surface Quadrats
  - Belt Transects
  - PLUS Tile Spat Collectors
- Compile with our historic data



# Monitoring Efforts: Elevation/Bathymetry

### • Project Reef Criteria


- Intertidal (-1.45ft NAVD88)
- 3:1 slope


### • **Surrounding Reef Change**

- Average Reef Height
- Oyster Density/Size Dist. and Elevation Relationship

Credit for 3D-work: Joe Aufmuth







# Varying Productivity in Tidal Creek Reefs



# Monitoring Efforts: WISH LIST

### Mapping:


- Intertidal/Subtidal Habitats
- Geomorphologic Change

#### • Sampling:

- Subtidal oyster
- · Benthic Macroinvertebrate
- Nekton
- Bird

#### Modeling:

- Elucidate oyster population response to hydrologic change and harvest
- Intertidal and subtidal reef building dynamics and collapse thresholds





### Engage Cooperators:

- Potential large scale ecologic impacts
- Relate to/inform other oyster restoration projects

# Reef Construction Scheduled: July 1, 2018



